

[illegible]

Quotation For Daikin VRV System

As World's No.1 Airconditioning Company, we are committed to delivering airconditioning solutions that enhance the quality of life all around the world. We are creating value through innovative technologies. As a Global Industry frontrunner, we are carrying out Research and Development on the world's most advanced airconditioning technology.

ANNEXURE I

HIGH SIDE WORK

S.No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	Supply of Variable Refrigerant Volume Outdoor units with inverter technology scroll compressor , low noise propellor type aero spiral fan, Condenser coil with special acrylic pretreatment for improved resistance to salt corrosion,refrigerant shut off valves,safety devices, lead free PC boards suitable for operation on R410a and on 380 - 415 V, 50 Hz, 3 phase A/C supply etc. as per standards				
	Make: DAIKIN (Cooling Model)				
1	Supply of Variable Refrigerant Volume Outdoor units				
a	20 HP (Model: RXQ20ARY6) TOP DISCHARGE	No's	1	350656	350656
b	DGT JOINT	No's	1	5500	5500
2	Supply of 4-Way Cassette ACs with Wirless Remotes				
a	2.08 TR (Model: FXFSQ63ARV16)	No's	2	41881	83762
3	Supply of Hi-Wall ACs with Wirless Remotes				
a	1.65 TR (MODEL NO: FXAQ50ARVE6)	No's	6	27084	162504
b	1.04 TR (MODEL NO: FXAQ32ARVE6)	No's	6	24827	148962
c	0.83 TR (MODEL NO: FXAQ25ARVE6)	No's	2	24461	48922
	Total no.of IDU		16		
4	Supply of Refnet Joints	Nos	15	2500	37500
	DX UNIT				
1	Supply of High Wall 5 Star Inverter AC, Single Phase				
a	1.5 TR (MODEL NO: FTKM50UV16U)	Nos	3	36508	109523
TOTAL HIGH SIDE EQUIPMENT VALUE					947329
GST ON SUPPLY @28 %					265252
TOTAL EQUIPMENT VALUE WITH TAX					1212582

ANNEXURE II								
LOW SIDE JOB								
S.N.	DESCRIPTION	UNIT	QTY	Rate		Amount		Remarks
				Supply	Instl.	Supply	Instl.	
1	Lifiting ,Shifting,Positioning and Installation of Outdoor units	No's	1		7500		7500	
2	Lifiting, Shifting, Positioning of VRV Indoor Units.							
a	Cassette unit	No's	2		3000		6000	
b	Hi-Wall unit	No's	14		2000		28000	
3	Supply & Installation of copper refrigerant piping duly insulated with nitrile insulation of 19mm thickness for Gas Pipe and 13mm thickness for Liquid Pipe / Including supports Clamps etc and incl bends, couplings and necessary fittings, for R 410 A Site Pressure tested to 550 psi.	Rmt	180	1410	160	253800	28800	Qty consider as per site measurments
4	Pressure testing with nitrogen Gas, Vaccumising Including all consumables for all systems. Gas charging and commissioning R-410A. (20HP)	LOT	1	38500	16500	38500	16500	
5	Supply and Installation of cabling of size 2C x 1.5 Sqmm copper wire to be laid in heavy grade PVC conduit including all fixing and accessories as per the approved routing. At Petla Burg	Rmt	270	160	50	43200	13500	Qty consider as per site measurments
6	PVC insulated piping for condensate drain							
a	25/32 mm Dia	Rmt	70	210	60	14700	4200	Qty consider as per site measurments
b	40 mm	Rmt	30	240	60	7200	1800	Qty consider as per site measurments
7	Refnet Joints	Nos	15		500		7500	
8	ODU stands	Nos	1	7000	500	7000	500	
	DX SYSTEM							
1	Installation & Commissioning							
a	Split AC	Nos	3		2000		6000	
2	Condenser stand							
a	Split AC	Nos	3	950	200	2850	600	
BASIC VALUE						367250	120900	
GST @18%						66105	21762	
TOTAL LOW SIDE VALUE WITH TAX						576017		
Note : The actual quantities will be Variable as per site actual measurements (final bill as per actual measurments) only.								

Daikin VRV BOQ	
PROJECT: MATERNITY HOSPITAL (MGMH)	
Date: 16-11-2023	
TOTAL HIGH SIDE EQUIPEMENT VALUE	1212582
TOTAL LOW SIDE INSTALLATION VALUE	576017
TOTAL PROJECT CONTRACT VALUE	1,788,599

Note : The actual quantities will be Variable as per site actual measurements only.

Note : Delivery lead time wthin 4 to 6 week after advance payment.

TERMS AND CONDITIONS:

- 01) Payment terms for high side is 100% advance along with the order.
 - 02) Delivery: As per site requirement
 - 03) Civil works, False Ceiling work will not comes in our scope.
 - 04) Validity of this quote is up to 15 Days only.
 - 05) If requirement of extra material at site will charge extra at actual.
 - 06) Low side payment 50% advance along with work order,30% indoor,out door units instalation, 20% after VRV commissioning
 - 07) Core Cutting, Chipping, Civil works and Scuffolding are in customer's scope only**
- We hope the above is in line with your requirement & incase you need any further clarification, kindly do revert back to us.
- 08) Drain Pump for Split ac charges extra If required.

Very truly yours

For. COMFORT COOL SYSTEMS

Managing Directors

Mr.Govind Gupta & M.Suresh

Ph: 9885456671, 9885456672.