

[illegible]

Quotation For Daikin VRV System

As World's No.1 Airconditioning Company, we are committed to delivering airconditioning solutions that enhance the quality of life all around the world. We are creating value through innovative technologies. As a Global Industry frontrunner, we are carrying out Research and Development on the world's most advanced airconditioning technology.

ANNEXURE I

HIGH SIDE WORK

S.No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	Supply of Variable Refrigerent Volume Outdoor units with inverter technology scroll compressor , low noise propellor type aero spiral fan, Condenser coil with special acrylic pretreatment for improved resistance to salt corrosion,refrigerant shut off valves,safety devices, lead free PC boards suitable for operation on R410a and on 380 - 415 V, 50 Hz, 3 phase A/C supply etc. as per standards				
	Make: DAIKIN (Cooling Model)				
1	Supply of Variable Refrigerant Volume Outdoor units				
a	18 HP (Model: RXQ18ARY6) TOP DISCHARGE	No's	1	313299	313299
b	DGT JOINT	No's	1	6500	6500
2	Supply of 4-Way Cassette ACs with Wirless Remotes				
a	3.31 TR (Model: FXFSQ100ARV16)	No's	2	46330	92659
3	Supply of Hi-Wall ACs with Wirless Remotes				
a	1.65 TR (MODEL NO: FXAQ50ARVE6)	No's	4	27084	108336
b	1.04 TR (MODEL NO: FXAQ32ARVE6)	No's	4	24827	99308
c	0.83 TR (MODEL NO: FXAQ25ARVE6)	No's	1	24461	24461
	Total no.of IDU		11		
4	Supply of Refnet Joints	Nos	10	2500	25000
	DX UNIT				
1	Supply of High Wall 5 Star Inverter AC, Single Phase				
a	1.5 TR (MODEL NO: FTKM50UV16U)	Nos	1	36508	36508
b	1.0 TR (MODEL NO: FTKM35UV16W)	Nos	1	31438	31438
TOTAL HIGH SIDE EQUIPMENT VALUE					737509
GST ON SUPPLY @28 %					206503
TOTAL EQUIPMENT VALUE WITH TAX					944012

Daikin VRV BOQ	
PROJECT: MATERNITY HOSPITAL	
Date: 27-09-2023	
TOTAL HIGH SIDE EQUIPEMENT VALUE	944012
TOTAL LOW SIDE INSTALLATION VALUE	477605
TOTAL PROJECT CONTRACT VALUE	1,421,617

Note : The actual quantities will be Variable as per site actual measurements only.

Note : Delivery lead time within 4 to 6 week after advance payment.

TERMS AND CONDITIONS:

- 01) Payment terms for high side is 100% advance along with the order.
- 02) Delivery: As per site requirement
- 03) Civil works, False Ceiling work will not come in our scope.
- 04) Validity of this quote is up to 15 Days only.
- 05) If requirement of extra material at site will charge extra at actual.
- 06) Low side payment 50% advance along with work order, 30% indoor, out door units installation, 20% after VRV commissioning

07) Core Cutting, Chipping, Civil works and Scuffolding are in customer's scope only

We hope the above is in line with your requirement & in case you need any further clarification, kindly do revert back to us.

08) Drain Pump for Split ac charges extra If required.

Very truly yours

For. COMFORT COOL SYSTEMS

Managing Directors

Mr. Govind Gupta & M. Suresh

Ph: 9885456671, 9885456672.