



# ARCHITECTURE AND INTERIORS

## We Shape Best Visual Art

Flat No.16-31-488/101, 1st floor, Above Ratnadeep Super Market, 6th Phase, KPHB, Medchal, Hyderabad-500 072, Mobile: +91 9030344466, Ph: 040-35989536 Telangana, India.

### QUATATION

DATE:27-12-2023 **QUATATION NO:5445** NAME OF THE CLINT-ASTA INFRA SERVICES PVT LTD ADDRESS-ROAD NO-3, BANJARA HILLS, HYDERABAD-500 034 GST NO:36AAJCA4782H1ZF

SL.NO	PARTICULARS	RATE
1	Providing and fixing 75mm thick Non asbestos fibre reinforced aerated cement sandwich	230
	modules made out of light weight fibre reinforced aerated cement/concrete core composed of	
	Portland cement, flyash, binders etc and 4mm thick High pressure steam cured non asbestos	
	fibre cement standard board Density>1200kg/m3 confirming to IS 14862 and Type B category III of	
	ISO 8336 E tested as per AS 1530 part 3 and BS 476 Part 4,5,6,7 on either side of the core having	
	a tongue and groove on longitudinal side of the modules. These solid wall panel should be	
	equivalent to ISO 354-1985, ASTM 423-90 and BS 476 Part 22 1987, IS 8225-1987 modules are	
	erected/installed using galvanized iron steel tracks of 1mm thick and of size 15x77x25mm as	
	bottom track, 25x77x25mm as top track for fixing to the floor and top of the wall respectively	
	including all necessary materials required for erecting and fixing all panel	

### NOTE:

- The Rate Should Be Mention Exclusive GST. 1)
- Payment schedule:

40% as advance

25% after material dumping

20% after 70% work completion

15% after handover the project

- Any additional work other than mentioned in the above quoatation will be charged additional.
- Final estimation might vary according to the final measurements take after completion of work

#### BANK DETAILS:

NAME OF THE BANK:STATE BANK OF INDIA ACCOUNT NO:36712228148 IFSC CODE:SBIN0010098 BRANCH: KUKATPALLY

GST NO:36BKTPR2029E2ZW